

Decommissioning Estimate/Plan



Date: 10/18/2022
Calculated By: CG

Beecher Road
Yorkville, IL

This Decommissioning Estimate has been prepared by New Leaf Energy in an attempt to predict the cost associated with the removal of the proposed solar facility. The primary cost of decommissioning is the labor to dismantle and load as well as the cost of trucking and equipment. All material will be removed from the site, including the concrete equipment pads, which will be broken up at the site and hauled to the nearest transfer station.

No salvage values have been assumed in this calculation.

The following values were used in this Decommissioning Estimate:

System Specifications		Equipment & Material Removal Rates	
Number of Modules	9,724	Module Removal Rate (min/module)	1
Linear Feet of Racking (ft)	36,465	Rack Wiring Rem. Rate (min/mod)	0.25
Number of Inverters	2	Racking Dismantling Rate (min/LF)	0.2
Number of Transformers	2	Inverter Removal Rate (hr/unit)	0.5
Number of Tracker Motors	4	Transformer Removal Rate (hr/unit)	1
Electrical Wiring Length (ft)	4,094	Motor Removal Rate (hr/unit)	1
Number of Foundation Piles	2,210	Rack Loading Rate (min/LF)	0.1
Length of Perimeter Fence (ft)	4,171	Elect. Wiring Removal Rate (min/LF)	0.5
Number of Power Poles	5	Pile Rem. Rate (piles/day)	300
Access Rd Material Volume (YD)	913	Fence Removal Rate (min/LF)	1
Total Disturbed Area (SF)	27,886	Days req. to break up concrete pads	3
Total Fence Weight (lbs)	2,961	Days req. with Rough Grader	1
Total Racking Weight (lbs)	228,514	Days req. with Fine Grader	1
Total Foundation Pile Weight (lbs)	298,350	Total Truckloads Required	21
		Round-Trip Dist. to Trans. Sta.(miles)	5.8
		Round-Trip Time to Trans. Sta. (hr)	0.15
Labor and Equipment Costs		Energy Storage Decommissioning	
Labor Rate (\$/hr)	\$ 35.00	Number of Energy Storage Units	2
Operator Rate (\$/hr)	\$ 47.00	Battery Disposal Fee	\$ 25,000.00
Bobcat Cost (\$/hr)	\$ 101.90	Battery Loading Prep Time (hr)	32
Front End Loader Cost (\$/Day)	\$ 845.77	Battery Loading Time (hr)	8
Excavator Cost (\$/Day)	\$ 1,365.46		
Trucking Cost (\$/hr)	\$ 127.38		
Backhoe Cost (\$/hr)	\$ 101.90		
Power Pole Removal Cost (\$/pole)	\$ 1,500.00		
Grader Cost (\$/day)	\$ 1,324.70		
Gravel Export Cost (\$/YD)	\$ 8.00		
Loam Import Cost (\$/YD)	\$ 20.00		
Seeding Cost (\$/SF)	\$ 0.10		
Fuel Cost (\$/mile)	\$ 0.50		

Labor, Material, and Equipment Costs

1. Remove Modules

The solar modules are fastened to racking with clamps. They slide in a track. A laborer needs only unclamp the module and reach over and slide the module out of the track.

$$\text{Module Removal Rate} \cdot \text{Total Number of Solar Modules} \cdot \text{Labor Rate} = \text{Module Removal Cost}$$

Total = \$ 5,672.33

2. Remove Rack Wiring

The modules are plugged together in the same manner as an electrical cord from a light is plugged into a wall socket. The string wires are in a tray. A laborer needs only unplug the module, reach into the tray and remove the strands of wire.

$$\text{Wire Removal Rate} \cdot \text{Total Number of Solar Modules} \cdot \text{Labor Rate} = \text{Rack Wiring Removal Cost}$$

Total = \$ 1,418.08

3. Dismantle Racks

Tracker module racking primarily consists of torque tubes and a driveline. These are supported on driven piles. The torque tubes and driveline unbolt from the foundation piles.

$$\text{Linear feet of Racking} \cdot \text{Rack Dismantling Rate} \cdot \text{Labor Rate} = \text{Rack Dismantling Cost}$$

Total = \$ 4,254.25

4. Remove and Load Electrical Equipment

Electrical equipment includes transformers, inverters, and tracker motors.

$$(\text{Number of Inverters} \cdot \text{Inverter Removal Rate} + \text{Number of Transformers} \cdot \text{Transformer Removal Rate} + \text{Number of Motors} \cdot \text{Motor Removal Rate}) \cdot (\text{Operator Rate} + \text{Bobcat Cost}) = \text{Electrical Equipment Removal Cost}$$

Total = \$ 1,042.30

5. Break Up Concrete Pads

Concrete pads are broken up using an excavator and jackhammer.

$$\text{Number of Demolition Days} \cdot (\text{Excavator Cost} + \text{Operator Cost}) = \text{Total Concrete Pad Removal}$$

Total = \$ 3,665.31

6. Load Racks

Once the racking has been dismantled, it will be loaded onto trucks for removal from the site. The trucking cost associated with this line item represents the additional time a truck will be needed during loading. Please see item # 13 for the cost of trucking off-site.

$$\text{Linear feet of Racking} \cdot \text{Rack Loading Rate} \cdot (\text{Operator Cost} + \text{Front End Loader Cost} + \text{Trucking Cost}) = \text{Total Rack Removal Cost}$$

Total = \$ 16,790.61

7. Remove Electrical Wiring

Electrical wiring will be removed from all underground conduits.

$$\text{Cable Length} \cdot \text{Cable Removal Rate} \cdot (\text{Operator Cost} + \text{Backhoe Cost}) = \text{Total Cable Removal Cost}$$

Total = \$ 5,079.97

8. Remove Foundation Piles

Foundation piles will be pulled out of the ground and loaded onto a truck to be removed from site.

$$(\text{Total Number of Piles} / \text{Daily Pile Removal Rate}) \cdot (\text{Operator Rate} + \text{Excavator Cost}) = \text{Total Pile Removal Cost}$$

Total = \$ 19,243.13

9. Remove Fencing

Fencing posts, mesh, and foundations will be loaded onto a truck and removed from site. Trucking costs included in this line item are for the removal process. Trucking to a recycling facility are included in item #13.

$$(\text{Total Length of Fence} \cdot \text{Fence Removal Rate}) \cdot (\text{Operator Rate} + \text{Bobcat Cost} + \text{Trucking Cost}) = \text{Total = $ 19,205.72}$$

10. Remove Power Poles

Power poles will be removed and shipped off site.

$$\text{Number of Power Poles} \cdot \text{Pole Removal cost} = \text{Total Power Pole Removal Cost}$$

Total = \$ 7,500.00

11. Gravel Road Reclamation

Reclamation of the gravel access road will entail removing the gravel material and exporting it off site. The area will then be backfilled with loam and graded.

$$(Days\ with\ Rough\ Grader + Days\ with\ Fine\ Grader) \cdot (Grader\ Cost\ per\ Day + Operator\ Cost\ per\ Day) + [Roadway\ Material\ Volume \cdot (Gravel\ Export\ Cost + Loam\ Import\ Cost)] = \\ Gravel\ Road\ Reclamation\ Cost$$

Total = \$ 28,953.99

12. Seed Disturbed Areas

Seeding cost includes labor and materials for reseeding all disturbed areas including the reclaimed gravel road area, former electrical areas, and areas disturbed by racking foundation removal.

$$Seeding\ Cost \cdot Disturbed\ Area = \\ Total\ Seeding\ Cost$$

Total = \$ 2,788.61

13. Truck to Transfer Station

All material will be trucked to the nearest Transfer station that accepts construction material. The nearest transfer station is Groot Recycling & Waste Services

$$(Total\ Truckloads \cdot Roundtrip\ Distance \cdot Fuel\ Cost) + (Total\ Truckloads \cdot Round\ Trip\ Time \cdot \\ Trucking\ Cost) = \\ Total\ Trucking\ Cost\ to\ Transfer\ Station$$

Total = \$ 462.13

14. Remove and Dispose of Energy Storage Equipment

The battery units will be prepared for shipment and loaded onto a truck. A disposal fee will also be required for the disposal company to accept the batteries.

$$Number\ of\ Battery\ Units \cdot ((Loading\ Prep\ Time \cdot Labor\ Cost) + Loading\ Time \cdot (Labor\ Rate + \\ Bobcat\ Cost + Trucking\ Cost) + Disposal\ Fee) = \\ Total\ Energy\ Storage\ Removal\ and\ Disposal\ Cost$$

Total = \$ 56,468.40



Salvage Values

Salvage Value Not Included

Summary of Decommissioning Costs and Salvage Values

Line Item	Task	Cost
1	Module Removal	\$ 5,672.33
2	Rack Wiring Removal	\$ 1,418.08
3	Rack Dismantling	\$ 4,254.25
4	Electrical Equipment Loading and Removal	\$ 1,042.30
5	Break Up Concrete Pads	\$ 3,665.31
6	Load Racks	\$ 16,790.61
7	Electrical Wiring Removal	\$ 5,079.97
8	Foundation Pile Removal	\$ 19,243.13
9	Fence Removal	\$ 19,205.72
10	Power Pole Removal	\$ 7,500.00
11	Gravel Road Reclamation	\$ 28,953.99
12	Seed Disturbed Areas	\$ 2,788.61
13	Trucking to Transfer Station	\$ 462.13
14	Energy Storage System Removal	\$ 56,468.40
		Subtotal = \$ 172,544.85

Additional Item	Task	Value
Salvage Values Not Included		

Additional Item Subtotal \$ -

Present Value Total = \$ 172,544.85

Task	Future Value
------	--------------

Inflation

of Years= 25

Inflation Rate= 2.0%

Total • (1+ Inflation Rate)^Number of Years =Grand Total

Grand Total = \$ 283,078.11